BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20407

SCHEDULE-B

NAME OF WORK: Improvements to 13th B and C cross roads in Vishveshwaraiah layout in Bagalagunte Ward no.14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Gnanendra Murthy M D		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Scarifying kankar / gravel / metal crust upto 150mm thick with pick axes and disposal of stuff including cost of all labour charges Complete as per specifications.	Sqm	750.5	25.92	Rupees Twenty Five and Ninety Two Paise Only	19452.96
2	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification	Cum	337.73	311.04	Rupees Three Hundred Eleven and Four Paise Only	105047.54
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Cum	75.05	1500.0	Rupees One Thousand Five Hundred Only	112575.00
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	112.58	4900.0	Rupees Four Thousand Nine Hundred Only	551642.00

Signature of the Contractor

Executive Engineer

5	Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	112.58	4950.0	Rupees Four Thousand Nine Hundred Fifty Only	557271.00
6	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	Sqm	72	800.0	Rupees Eight Hundred Only	57600.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	750.5	80.33	Rupees Eighty and Thirty Three Paise Only	60287.67
					Total	1463876.16
					Percentage	-7.28%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
DTS COPY

NAME OF THE WORK: Improvements to 13th B and C cross roads in Vishveshwaraiah layout in Bagalagunte Ward no.14

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Scarifying kankar / gravel / metal crust upto 150mm thick with pick axes and disposal of stuff including cost of all labour charges Complete as per specifications. As per the direction of Engg. charge.	Sqm	750.50		
2	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification as per directed by the Engineer in charge of the work.	Cum	337.73		
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Cum	75.05		
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. as per directed by the Engineer in charge of the work	Cum	112.58		
5	Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. as per directed by the Engineer in charge of the work	Cum	112.58		

Signature of the Contractor

Number of Corrections Nil

Executive Engineer
Dasarahalli Division

6	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications as per directed by the Engineer in charge of the works	Sqm	72.00		
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading as per directed by the Engineer in charge of the works	Cum	750.50		

Number of Corrections: Nil 7 Nos

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

DTS Approved

Chief Engineer
Bruhat Bangalore Mahanagara Palike
Dasarahalli Zone, Bangalore

Signature of the Contractor

Number of Corrections

Executive Engineer
Dasarahalli Division